

AD-A267 567



2

ARMY RESEARCH LABORATORY




# Response Surface Analysis of the SHOGUN Tube/Projectile Interface Model

David A. Hopkins  
James C. Ford

ARL-TR-164

July 1993



93-17404



2405

APPROVED FOR PUBLIC RELEASE; DISTRIBUTION IS UNLIMITED.

93

8

3

099

## NOTICES

Destroy this report when it is no longer needed. DO NOT return it to the originator.

Additional copies of this report may be obtained from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Road, Springfield, VA 22161.

The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

The use of trade names or manufacturers' names in this report does not constitute indorsement of any commercial product.

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE July 1993		3. REPORT TYPE AND DATES COVERED Final, April - June 1991
4. TITLE AND SUBTITLE Response Surface Analysis of the SHOGUN Tube/Projectile Interface Model			5. FUNDING NUMBERS PR: 1L162618AH80	
6. AUTHOR(S) David A. Hopkins and James C. Ford				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) U.S. Army Research Laboratory ATTN: AMSRL-WT-PD Aberdeen Proving Ground, MD 21005-5066			8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) U.S. Army Research Laboratory ATTN: AMSRL-OP-CI-B (Tech Lib) Aberdeen Proving Ground, MD 21005-5066			10. SPONSORING/MONITORING AGENCY REPORT NUMBER ARL-TR-164	
11. SUPPLEMENTARY NOTES				
12a. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution is unlimited.			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words)  Prediction of the dynamic response of a projectile fired from a gun tube requires estimation of the interface loads between the gun tube and the projectile. Interface models have been developed to determine the loads induced by interaction between the gun tube and the projectile. The model incorporated in the SHOGUN gun dynamics code models the interface as a collection of linear and torsional springs. Precise values for the spring stiffness coefficients are not known. The effect of uncertainties in these coefficients upon the shot exit conditions of the projectile can be evaluated using experimental design methodology. In this report, the response surfaces for two projectile shot exit parameters are examined. This methodology is shown to provide several benefits over the typical method of parametric sensitivity studies. It is also shown how this method can reveal idiosyncracies in the interface model which may not be revealed using a typical sensitivity study.				
14. SUBJECT TERMS statistical design, metamodeling, gun tube interface models, models, response surface methodology (RSM), computerized simulation			15. NUMBER OF PAGES 20	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED	18. SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED	19. SECURITY CLASSIFICATION OF ABSTRACT UNCLASSIFIED	20. LIMITATION OF ABSTRACT UL	

INTENTIONALLY LEFT BLANK.

## TABLE OF CONTENTS

	<u>Page</u>
LIST OF FIGURES .....	v
LIST OF TABLES .....	v
1. INTRODUCTION .....	1
2. ANALYSIS .....	2
3. DISCUSSION .....	5
4. CONCLUSIONS .....	10
5. REFERENCES .....	11
DISTRIBUTION LIST .....	13

INTENTIONALLY LEFT BLANK.

## LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
1. Gun tube/projectile interface model .....	3
2. Three-factor face-centered cube design .....	4
3. Crossing velocity angular value .....	6
4. Angular velocity angular value .....	6
5. Contour plot of crossing velocity angular value .....	7
6. Contour plot of angular velocity angular value .....	8

## LIST OF TABLES

<u>Table</u>	<u>Page</u>
1. Range of Factor Values .....	2
2. Coefficient Values for Selected Responses .....	5
3. Comparison of Actual and Predicted Response Values .....	10

**DTIC QUALITY INSPECTED 3**

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Date _____	

A-1

INTENTIONALLY LEFT BLANK.

## 1. INTRODUCTION

The dynamic response of a projectile traveling in a gun tube is influenced by the material and geometric properties of the components of the gun system and the manner in which these components interact. The two primary components of the gun system which are typically considered are the gun tube and the projectile. The detail with which these components are modeled depends upon the intended application. Complex finite element (FE) models in which fine details are included are normally related to stress analysis predictions in which the survivability of the projectile components is of primary concern (Wilkerson 1990). Less detailed beam models which are capable of capturing the basic gross deformation of the projectile and tube during firing are routinely used to determine quantities such as the rigid body motion of the projectile during shot exit (Erline and Kregel 1990; Hopkins 1990).

Both modeling approaches require a means to determine the interaction forces which develop between the projectile and the gun tube during the interior ballistic cycle. The FE models use slideline techniques (Hallquist 1978). Changes in the projectile geometry are reflected by changes in the interface loads determined by the slideline algorithms. While accurate, these algorithms are often very complex and can result in substantial increases in computer execution time. The simpler beam models employ interface routines which attempt to model the tube/projectile interaction by a combination of linear and torsional springs which are compressed by the relative displacements between the gun and projectile components (Erline and Kregel 1990; Soifer and Becker 1987). These simpler models do not lead to substantial increases in computer execution times. However, valid values for the spring coefficients for different projectile geometries are difficult to determine.

Numerous iterations of an analysis may be required to determine the effect of changes in projectile design when the goal of the simulation is the determination of the effect of the interaction loads upon some characteristic of the dynamic response of the projectile. These iterations can be costly either because of increased computer time required by the FE models or additional runs required by the simpler beam models to explore the effects in uncertainties regarding appropriate spring coefficients. This iterative process is often referred to as a parametric or sensitivity study. The number of iterations required in the parametric study can be reduced while simultaneously increasing the quality of information obtained using experimental design methodology (E. I. Du Pont de Nemours & Co. 1988). The applicability of experimental design in computer simulation is illustrated in this paper by examining the dynamic response characteristics of a projectile to changes in the interface spring stiffness coefficients which determine the

loads between the projectile and gun tube in the interface model used in the SHOGUN gun dynamics code. The primary goal of the study is the determination of the response surfaces for two of the projectile shot exit rigid body motion parameters. Results for the predicted response surface of the angle of the crossing velocity vector,  $\theta_v$ , and the angle of the angular velocity vector,  $\theta_\psi$ , during shot exit are presented.

## 2. ANALYSIS

The interface between the gun and the projectile is modeled in SHOGUN as interacting beams coupled by linear and torsional springs (Figure 1). The linear spring describing the forward spring connection,  $X_3$ , can also have a clearance which is used to simulate impact. Altogether, there are seven parameters in the interface model. In this paper, only four of these parameters are varied. These four parameters are the two linear,  $X_1$  and  $X_3$ , and two torsional,  $X_2$  and  $X_4$ , spring coefficients. The ranges of these parameters are listed in Table 1. Shogun does not specify allowable values for these parameters, the ranges selected are intended to encompass values that may be considered reasonable. The order of magnitude of these values is based upon consideration of the actual structural stiffness of the components which the springs represent.

Table 1. Range of Factor Values

Factor	Value	
	Low	High
$X_1(\text{lb/in})$	$1.0 \times 10^3$	$200.0 \times 10^6$
$X_2(\text{in lb/rad})$	0.0	$20.0 \times 10^6$
$X_3(\text{lb/in})$	$1.0 \times 10^3$	$20.0 \times 10^6$
$X_4(\text{in lb/rad})$	0.0	$2.0 \times 10^6$

The three parameters not examined correspond to the clearance between the forward bell and the gun tube, and to two spring stiffness coefficients which couple angular displacement with radial loads. The clearance was not included in this study simply to reduce the complexity of the analysis. The effects of the spring stiffness coefficients which couple angular displacement with radial loads were not included




Figure 1. Gun tube/projectile interface model.

because the appropriateness and validity of these parameters is doubtful. For this study, the clearance was set to a fixed value of 0.004 in, based on projectile drawings, while the neglected stiffness coefficients were set to zero.

A face-centered cube (FCC) experimental design is used to determine which combination of values of the spring stiffness coefficients is used to generate the response surfaces. There are two primary reasons for using the FCC design. First, the data obtained allows precise estimation of the coefficients of a predictive equation. Second, the FCC design obtains information concerning the effects of the independent variables, called factors, at the extremes of high/low for each factor. A predictive equation is thus obtained which spans the entire factor space. These concepts are easily explained visually using an FCC design for three factors (Figure 2). It is seen that 15 data points are required—one at each corner, one at the center of each face, and one at the center of the cube. This design does not require replication of any individual data point. The corner points represent the extreme values of the factors. The midrange data point locations allow the determination of interaction and curvature effects. In this study, the FCC design for four factors requires a total of 25 data points to map the response surface. A deterministic process is one for which the system error is identically zero. This is the case for FE analysis since results




Figure 2. Three-factor face-centered cube.

for a given problem will not change from one computer run to the next. Thus, SHOGUN is a deterministic process.

Two response surfaces have been generated: the angle of the crossing velocity vector,  $\theta_v$ , and the angle of the angular velocity vector,  $\theta_{\dot{\psi}}$ , during shot exit. These responses have been selected to illustrate the utility of the technique. The data gathered reveal that the torsional spring,  $X_4$ , does not affect the observed responses. Consequently, this factor is not considered in the subsequent numerical analysis of the data.

For each response, a quadratic polynomial of the form

$$\begin{aligned}
 Y = & b_0 + b_1 Z_1 + b_2 Z_2 + b_3 Z_3 \\
 & + b_{12} Z_1 Z_2 + b_{13} Z_1 Z_3 \\
 & + b_{23} Z_2 Z_3 + b_{11} Z_1^2 \\
 & + b_{22} Z_2^2 + b_{33} Z_3^2,
 \end{aligned}$$

where  $Z_i = (X_i)^{1/2}$ , is used to generate the response surface. This polynomial representation includes all linear, quadratic, and two-way interactions between the factors. A standard regression analysis is used to compute the coefficients of the polynomial. The units of these coefficients are simply those required to convert the response to radians. Thus, the units of  $b_0$  is radians,  $b_1$  and  $b_3$  are  $(\text{rad}^2 \text{ lb/in})^{1/2}$ ,  $b_2$  is  $(\text{rad}/(\text{in-lb}))^{1/2}$ , etc. The coefficients of the polynomials for  $\theta_v$  and  $\theta_\psi$  are presented in Table 2. Response surfaces for  $\theta_v$  and  $\theta_\psi$ , obtained for a constant value of  $X_3$ , are shown in Figures 3 and 4, respectively. Contour plots obtained from these surfaces are shown in Figures 5 and 6. Contour plots are projections of the response surface onto the  $Z_1Z_2$  plane. The  $Z_1Z_2$  plane corresponds to the square root of the range of values that can be used for the linear and torsional spring parameters of the obturator. Thus, this plane represents, indirectly through these stiffness parameters, the geometry of the obturator and the effect of the geometry on stiffness.

Table 2. Coefficient Values for Selected Responses

Y	$b_0$	$b_1 \times 10^{-3}$	$b_2 \times 10^{-3}$	$b_3 \times 10^{-3}$	$b_{12} \times 10^{-8}$	$b_{13} \times 10^{-8}$	$b_{23} \times 10^{-8}$	$b_{11} \times 10^{-8}$	$b_{22} \times 10^{-8}$	$b_{33} \times 10^{-8}$	$R^2_{adj}$	RMS Error
$\theta_v$	5.26	0.21	0.35	-1.40	-1.56	6.93	5.88	0.08	-5.10	10.21	0.87	0.47
$\theta_\psi$	2.21	0.10	1.48	-0.89	-4.26	-1.41	6.27	0.15	-23.88	20.78	0.86	0.37

### 3. DISCUSSION

In the previous section, response surfaces were generated by fitting the data to a second-order polynomial. The selection of this polynomial represents a rudimentary model which is capable of capturing both curvature and interaction effects. No transformations were used on the responses  $\theta_v$  and  $\theta_\psi$ . However, the factors  $X_1$ ,  $X_2$ , and  $X_3$  were transformed using terms in powers of the square root of the factors. The square root transformation was selected based on the following observation. Examining Figure 1, it is reasonable to expect the interface model to behave in some sense like a simple spring-mass vibrating system. For this type of behavior, the response is proportional to the frequency of the system, which is, in turn, proportional to the square root of the stiffness (Meirovitch 1967).

The degree of success with which the response surfaces are represented can be quantified by examining the value of the adjusted  $R^2$ . Since there is no experimental error,  $R^2_{adj}$  represents the goodness

$z_3 = 2251.879366$




Figure 3. Crossing velocity angular value.

$z_3 = 2251.879366$




Figure 4. Angular velocity angular value.




Figure 5. Contour plot of crossing velocity angular value.




Figure 6. Contour plot of angular velocity angular value.

of fit of the model.  $R_{adj}^2$  values for both models are listed in Table 2. For  $\theta_v$ ,  $R_{adj}^2$  is 0.87; while for  $\theta_\psi$ ,  $R_{adj}^2$  is 0.86. This means that 87% or 86% of the total variation in the response of  $\theta_v$  or  $\theta_\psi$ , respectively, is explained by the model. The residual mean square (RMS) error is 0.47 and 0.37 for the two responses, respectively. Generally, the RMS error is a direct estimate of the combination of system error and model lack-of-fit. Since system error in this study is zero, the RMS error indicates directly the goodness-of-fit of the response surface to the exact surface over the entire range of the factors. Another means of checking the accuracy of the response surface models is by comparing the predicted values of  $\theta_v$  and  $\theta_\psi$  with the actual results of SHOGUN which were used to generate the surfaces. This comparison is shown in Table 3. It is noted that there are several points which exceed the RMS error estimate by appreciable amounts. Although not perfect, the overall goodness-of-fit of the response surface models is adequate to capture the basic topology of the response surfaces.

The fact that factor  $X_4$  does not affect the observed responses in any manner is disconcerting. There are four possible explanations for this behavior. First, it is possible that over the range selected, there is indeed absolutely no contribution to the response which can be attributed to  $X_4$ . This is highly improbable. Second,  $X_4$  is affected by the value of the clearance parameter. The clearance parameter is one of the parameters held constant in this study. It is possible that the  $X_4$  value selected allowed  $X_3$  to affect the response while constraining any effect due to  $X_4$ . Third, there may be a coding error in the SHOGUN loading algorithm. Fourth, the SHOGUN interface model may not correctly model the effect of  $X_4$ . At this point, it is not known which of these explanations is correct.

The two response surfaces illustrate several important features. Consider the response surface for  $\theta_v$ . The overall shape is basically a conic section. The minimum value of  $\theta_v$  for a fixed value of  $X_3$  occurs when  $X_1$  is maximized and  $X_2$  is minimized. This can be seen directly from Figure 3. The maximum response for  $\theta_v$  is obtained when  $X_1$  is minimized and  $X_2$  is maximized. Generally, increasing  $X_1$  while decreasing  $X_2$ , at a fixed value of  $X_3$ , results in a lower value of  $\theta_v$ .

Next, consider the response surface for  $\theta_\psi$ , which has a saddle point. The minimum value of  $\theta_\psi$  is obtained when  $X_1$  and  $X_2$  are both minimized. However, in this region, relatively small changes in either factor result in relatively large changes in the response  $\theta_\psi$  when compared to the saddle region of Figure 6. This saddle region is often referred to as a "robust" region. If sensitivity of  $\theta_\psi$  to variations in  $X_1$  and  $X_2$  is to be minimized, then values of  $X_1$  and  $X_2$  should be selected such that the response is in the saddle region. From Figure 6, the desired ranges are thus  $64 \times 10^6 < X_1 < 200 \times 10^6$  and  $4 \times 10^6 < X_2 < 10 \times 10^6$ . In this region, the response is approximately 3.6 radians.

Table 3. Comparison of Actual and Predicted Response Values

Factors			$\theta_v$ (rad)		$\theta_{\psi}$ (rad)	
$X_1$ (lb/in)	$X_2$ (in-lb/rad)	$X_3$ (lb/in)	Actual	Predicted	Actual	Predicted
$1(10^3)$	0	$1(10^3)$	5.5148	5.2044	2.2737	2.1873
$200(10^6)$	0	$1(10^3)$	2.1941	2.4140	3.7980	3.8907
$1(10^3)$	$20(10^6)$	$1(10^3)$	5.6086	5.7613	3.9130	4.0244
$200(10^6)$	$20(10^6)$	$1(10^3)$	2.4694	1.9853	3.1472	3.0371
$1(10^3)$	0	$20(10^6)$	.7462	1.0570	2.2697	2.3810
$200(10^6)$	0	$20(10^6)$	2.7105	2.6094	3.3102	3.2003
$1(10^6)$	$20(10^6)$	$20(10^6)$	3.0438	2.7805	5.5231	5.4628
$200(10^6)$	$20(10^6)$	$20(10^6)$	2.8527	3.3473	3.5512	3.5914
$1(10^3)$	$10(10^6)$	$10(10^6)$	2.8187	3.0481	4.5347	4.3801
$200(10^6)$	$10(10^6)$	$10(10^6)$	2.8689	2.6226	3.3285	3.5576
$100(10^6)$	0	$10(10^6)$	2.2591	2.0213	3.2197	2.1729
$100(10^6)$	$20(10^6)$	$10(10^6)$	2.4841	2.7044	2.9335	2.9867
$100(10^6)$	$10(10^6)$	$1(10^3)$	2.4578	3.3134	2.3167	4.2730
$100(10^6)$	$10(10^6)$	$20(10^6)$	3.9311	3.0589	4.6690	4.7222
$100(10^6)$	$10(10^6)$	$10(10^6)$	2.7004	2.7153	3.7685	3.7374

#### 4. CONCLUSIONS

Using techniques of statistical design, response surfaces for two measures of projectile behavior have been generated. The generation of these surfaces requires 25 data points. These response surfaces are adequate to determine the relative influence of the stiffness coefficients used to model the tube/projectile interface in the SHOGUN gun dynamics code. The response  $\theta_{\psi}$  can be strongly affected by changes in either  $X_1$  or  $X_2$ . However, because the response surface for  $\theta_{\psi}$  exhibits a saddle point, the sensitivity of  $\theta_{\psi}$  to change in  $X_1$ , or  $X_2$  can be mitigated by keeping the values of these parameters within the range of values defined by the saddle region.

Since the goal of this report was to introduce the reader to the fundamentals of response surface analysis and experimental design as applied to computer simulation, the response  $X_3$  was only analyzed at one level. Hence, no definitive conclusions can be drawn.

The factor  $X_4$  did not have any effect upon the responses selected. Several possible reasons for this observation have been postulated, but at present the correct explanation is not known.

## 5. REFERENCES

- E. I. Du Pont de Nemours & Co. Strategy of Experimentation, Planning and Analyzing Efficient Experiments. Quality Management and Technology Center, Newark, DE, 1988.
- Erline, T., and M. D. Kregel. "Modeling Gun Dynamics with Dominant Loads." BRL MR-3683, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, July 1988.
- Hallquist, J. O. "A Numerical Treatment of Sliding Interfaces and Impact." Computational Techniques for Interface Problems, edited by K. C. Park and D. K. Gartling. Applied Mechanics Division, ASME, vol. 30, p. 117-133, New York, 1978.
- Hopkins, D. A. "Modeling Gun Dynamics with Three-Dimensional Beam Elements." BRL-MR-3171, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, July 1990.
- Meirovitch, L. Analytical Methods in Vibration. New York: MacMillan Company, 1967.
- Soifer, M., and R. Becker. "Dynamic Analysis of the 120-mm Tank Gun." BRL-CR-576, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, June 1991.
- Wilkerson, S. "The Use of Advanced Transient Structural Codes to Study Interior Gun Dynamics." Proceedings of the ASME CIE Conference, Santa Clara, CA, 28 July-1 August 1991.

INTENTIONALLY LEFT BLANK.

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
2	Administrator Defense Technical Info Center ATTN: DTIC-DDA Cameron Station Alexandria, VA 22304-6145	1	Commander U.S. Army Missile Command ATTN: AMSMI-RD-CS-R (DOC) Redstone Arsenal, AL 35898-5010
1	Commander U.S. Army Materiel Command ATTN: AMCAM 5001 Eisenhower Ave. Alexandria, VA 22333-0001	1	Commander U.S. Army Tank-Automotive Command ATTN: AMSTA-JSK (Armor Eng. Br.) Warren, MI 48397-5000
1	Director U.S. Army Research Laboratory ATTN: AMSRL-OP-CI-AD, Tech Publishing 2800 Powder Mill Rd. Adelphi, MD 20783-1145	1	Director U.S. Army TRADOC Analysis Command ATTN: ATRC-WSR White Sands Missile Range, NM 88002-5502
1	Director U.S. Army Research Laboratory ATTN: AMSRL-OP-CI-AD, Records Management 2800 Powder Mill Rd. Adelphi, MD 20783-1145	1	Commandant U.S. Army Field Artillery School ATTN: ATSF-CSI Ft. Sill, OK 73503-5000
2	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-IMI-I Picatinny Arsenal, NJ 07806-5000	(Class. only) 1	Commandant U.S. Army Infantry School ATTN: ATSH-CD (Security Mgr.) Fort Benning, GA 31905-5660
2	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-TDC Picatinny Arsenal, NJ 07806-5000	(Unclass. only) 1	Commandant U.S. Army Infantry School ATTN: ATSH-CD-CSO-OR Fort Benning, GA 31905-5660
1	Director Benet Weapons Laboratory U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-CCB-TL Watervliet, NY 12189-4050	1	WL/MNOI Eglin AFB, FL 32542-5000
1	Director U.S. Army Aviation Research and Technology Activity ATTN: SAVRT-R (Library) M/S 219-3 Ames Research Center Moffett Field, CA 94035-1000		<u>Aberdeen Proving Ground</u>
		2	Dir, USAMSAA ATTN: AMXSY-D AMXSY-MP, H. Cohen
		1	Cdr, USATECOM ATTN: AMSTE-TC
		1	Dir, ERDEC ATTN: SCBRD-RT
		1	Cdr, CBDA ATTN: AMSCB-CII
		1	Dir, USARL ATTN: AMSRL-SL-I
		10	Dir, USARL ATTN: AMSRL-OP-CI-B (Tech Lib)

<u>No. of Copies</u>	<u>Organization</u>
11	<p>Director Benet Weapons Laboratory U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-CCB, F. Heizer J. Keane T. Allen J. Vasilakis G. Friar J. Zweig T. Simkins V. Montvori J. Wrzochalski G. D'Andrea R. Hasenbein Watervliet, NY 12189</p>
2	<p>Commander Watervliet Arsenal ATTN: SMCWV-AQE-Q, C. Howd, Bldg. 44 ATTN: SMCWV-SPM, T. McCloskey, Bldg. 25/3 Watervliet, NY 12189-4050</p>
9	<p>Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-CCH-T, S. Musalli P. Christian K. Fehsal N. Krasnow R. Carr SMCAR-CCH-V, E. Fennell SMCAR-CCH, J. DeLorenzo SMCAR-CC, J. Hedderich SMCAR-CCH-P, J. Lutz Picatinny Arsenal, NJ 07806-5000</p>
3	<p>Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-TD, R. Price V. Linder T. Davidson Picatinny Arsenal, NJ 07806-5000</p>

<u>No. of Copies</u>	<u>Organization</u>
1	<p>Commander Production Base Modernization Activity U.S. Army Armament Research, Development, and Engineering Center ATTN: AMSMC-PBM-K Picatinny Arsenal, NJ 07806-5000</p>
1	<p>Commander U.S. Army Belvoir RD&amp;E Center ATTN: STRBE-JBC, C. Kominos Fort Belvoir, VA 22060-5606</p>
2	<p>Commander U.S. Army Missile Command ATTN: AMSMI-RD, W. McCorkle AMSMI-RD-ST, P. Doyle Redstone Arsenal, AL 35898</p>
3	<p>Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-FSA-M, R. Botticelli F. Diorio SMCAR-FSA, C. Spinelli Picatinny Arsenal, NJ 07806-5000</p>
3	<p>Project Manager Advanced Field Artillery System ATTN: COL Napoliello LTC A. Ellis G. DelCoco Picatinny Arsenal, NJ 07806-5000</p>
2	<p>Commander Watervliet Arsenal ATTN: SMCWV-QA-QS, K. Insco Watervliet, NY 12189-4050</p>
2	<p>Project Manager SADARM Picatinny Arsenal, NJ 07806-5000</p>

<u>No. of Copies</u>	<u>Organization</u>
7	Project Manager Tank Main Armament Systems ATTN: SFAE-AR-TMA, COL Hartline C. Kimker SFAE-AR-TMA-MD, H. Yuen J. McGreen SFAE-AR-TMA-ME, R. Joinson D. Guzowitz SFAE-AR-TMA-MP, W. Lang Picatinny Arsenal, NJ 07806-5000
1	U.S. Army Research Laboratory Advanced Concepts and Plans ATTN: AMSRL-CP-CA, D. Snider 2800 Powder Mill Road Adelphi, MD 20783
1	U.S. Army Materiel Command ATTN: AMCDCG-T, R. Chait 5001 Eisenhower Ave. Alexandria, VA 22333-001
2	PEO-Armaments ATTN: SFAE-AR-PM, D. Adams T. McWilliams Picatinny Arsenal, NJ 07806-5000
2	U.S. Army Research Office ATTN: Andrew Crowson AMXRO-MCS, J. Chandra P.O. Box 12211 Research Triangle Park, NC 27709-2211
2	NASA Langley Research Center Mail Stop 266 ATTN: F. Barlett, Jr. AMSRL-VS, W. Elber Hampton, VA 23681-0001
2	Commander DARPA ATTN: J. Kelly B. Wilcox 3701 North Fairfax Drive Arlington, VA 22203-1714

<u>No. of Copies</u>	<u>Organization</u>
6	Director U.S. Army Research Laboratory Materials Directorate ATTN: AMSRL-MA-P, L. Johnson B. Halpin T. Chou AMSRL-MA-PA, D. Granville W. Haskell AMSRL-MA-MA, G. Hagnauer Watertown, MA 02172-0001
1	Commander Wright-Patterson Air Force Base ATTN: AFWAML, R. Kim Dayton, OH 45433
1	Naval Research Laboratory Code 6383 ATTN: I. Wolock Washington, DC 20375-5000
1	Office of Naval Research Mech Div Code 1132SM ATTN: Yapa Rajapakse Arlington, VA 22217
2	David Taylor Research Center ATTN: R. Rockwell W. Phyllaier Bethesda, MD 20054-5000
1	David Taylor Research Center Ship Structures and Protection Department ATTN: J. Corrado, Code 1702 Bethesda, MD 20084
4	Director Lawrence Livermore National Laboratory ATTN: R. Christensen S. deTeresa W. Feng F. Magness P.O. Box 808 Livermore, CA 94550

<u>No. of Copies</u>	<u>Organization</u>
2	Pacific Northwest Laboratory A Div of Battelle Memorial Inst. Technical Information Section ATTN: M. Smith M. Garnich P.O. Box 999 Richland, WA 99352
6	Director Sandia National Laboratories Applied Mechanics Department, Division 8241 ATTN: C. Robinson G. Benedetti W. Kawahara K. Perano K. Dawson P. Nielan P.O. Box 969 Livermore, CA 94550-0096
1	Director Los Alamos National Laboratory ATTN: D. Rabern MEE-13, Mail Stop J-576 P.O. Box 1633 Los Alamos, NM 87545
2	Virginia Polytechnical Institute and State University Dept. of ESM ATTN: Michael W. Hyer Kenneth L. Reifsnider Blacksburg, VA 24061-0219
2	University of Dayton Research Institute ATTN: Ran Y. Kim Ajit K. Roy 300 College Park Avenue Dayton, OH 45469-0168
1	Drexel University ATTN: Albert S. D. Wang 32nd and Chestnut Streets Philadelphia, PA 19104
1	University of Dayton ATTN: James M. Whitney 300 College Park Avenue Dayton, OH 45469-0240

<u>No. of Copies</u>	<u>Organization</u>
1	Purdue University School of Aero & Astro ATTN: C. T. Sun W. Lafayette, IN 47907-1282
1	University of Kentucky ATTN: Lynn Penn 763 Anderson Hall Lexington, KY 40506-0046
3	University of Delaware Center for Composite Materials ATTN: J. Gillespe B. Pipes M. Santare 201 Spencer Laboratory Newark, DE 19716
2	North Carolina State University Civil Engineering Department ATTN: W. Rasdorf L. Spainhour P.O. Box 7908 Raleigh, NC 27696-7908
1	University of Utah Department of Mechanical and Industrial Engineering ATTN: S. Swanson Salt Lake City, UT 84112
1	Stanford University Department of Aeronautics and Aeroballistics Durant Building ATTN: S. Tsai Stanford, CA 94305
1	Pennsylvania State University ATTN: Renata S. Engel 245 Hammond Building University Park, PA 16801
1	Pennsylvania State University ATTN: David W. Jensen 223-N Hammond University Park, PA 16802

<u>No. of Copies</u>	<u>Organization</u>
1	Pennsylvania State University ATTN: Richard McNitt 227 Hammond Bldg. University Park, PA 16802
1	UCLA MANE Dept., Engineering IV ATTN: H. Thomas Hahn Los Angeles, CA 90024-1597
1	University of Illinois at Urbana-Champaign National Center for Composite Materials Research 216 Talbot Laboratory ATTN: J. Economy 104 South Wright Street Urbana, IL 61801
2	Olin Corporation Flinchbaugh Division ATTN: E. Steiner B. Stewart P.O. Box 127 Red Lion, PA 17356
1	Olin Corporation ATTN: L. Whitmore 10101 9th St., North St. Petersburg, FL 33702
3	Alliant Techsystems, Inc. ATTN: C. Candland J. Bode K. Ward 5901 Lincoln Dr. Minnetonka, MN 55346-1674
1	Alliant Techsystems, Inc. Precision Armaments Systems Group 7225 Northland Drive Brooklyn Park, MN 55428
1	Chamberlain Manufacturing Corporation Research and Development Division ATTN: T. Lynch 550 Esther Street P.O. Box 2335 Waterloo, IA 50704

<u>No. of Copies</u>	<u>Organization</u>
1	Custom Analytical Engineering Systems, Inc. ATTN: A. Alexander Star Route, Box 4A Flintstone, MD 21530
2	Institute for Advanced Technology ATTN: T. Kiehne H. Fair 4030-2 W. Braker Lane Austin, TX 78759
2	Kaman Sciences Corporation ATTN: D. Elder J. Betz P.O. Box 7463 Colorado Springs, CO 80933
3	LORAL/Vought Systems ATTN: G. Jackson K. Cook L. L. Hadden 1701 West Marshall Drive Grand Prairie, TX 75051
1	Interferometrics, Inc. ATTN: R. Larriva, Vice President 8150 Leesburg Pike Vienna, VA 22100
1	ARMTEC Defense Products ATTN: Steve Dyer 85-901 Avenue 53 P.O. Box 848 Coachella, CA 92236
9	Director U.S. Army Research Laboratory ATTN: AMSRL-WT-PD-(ALC), A. Abrahamian K. Barnes M. Berman H. Davison A. Frydman T. Li W. McIntosh E. Szymanski H. Watkins 2800 Powder Mill Road Adelphi, MD 20783-1145

No. of  
Copies    Organization

Aberdeen Proving Ground

62    Dir, USARL  
 ATTN: AMSRL-SL-B, P. Deitz (328)  
       AMSRL-SL-BA, J. Walbert (1065)  
       AMSRL-SL-BL, D. Bely (328)  
       AMSRL-WT, A. Barrows  
       AMSRL-WT-W, C. Murphy  
       AMSRL-WT-WC, J. Rocchio  
       AMSRL-WT-WE,  
       J. Temperley  
       J. Groff  
       J. Thomas  
       AMSRL-WT-WA,  
       H. Rogers  
       B. Moore  
       A. Baran  
       AMSRL-WT-WB,  
       F. Brandon  
       W. D'Amico  
       AMSRL-CI, W. Mermagen  
       AMSRL-CI-CB, R. Kaste  
       AMSRL-CI-C, W. Sturek  
       AMSRL-CI-S, A. Mark  
       AMSRL-WT-T, W. Morrison  
       AMSRL-WT-TD,  
       D. Dietrich  
       G. Randers-Pehrson  
       J. Huffington  
       A. Das Gupta  
       J. Santiago  
       AMSRL-WT-TC,  
       K. Kimsey  
       R. Coates  
       W. de Rosset  
       L. Giglio-tos  
       AMSRL-WT-TA,  
       W. Gillich  
       W. Bruchey  
       AMSRL-WT-P, I. May  
       AMSRL-WT-PE,  
       A. Horst, Jr.  
       T. Minor  
       D. Kooker  
       AMSRL-WT-PA, C. Leveritt  
       AMSRL-WT-PB,  
       E. Schmidt  
       P. Plostins  
       B. Held

No. of  
Copies    Organization

AMSRL-WT-PD,  
 B. Burns  
 W. Drysdale  
 K. Bannister  
 T. Bogetti  
 J. Bender  
 J. Ford (5 cps)  
 R. Murray  
 R. Kirkendall  
 T. Erline  
 D. Hopkins (5 cps)  
 S. Wilkerson  
 C. McCall  
 D. Henry  
 R. Kaste  
 L. Burton  
 J. Tzeng

## USER EVALUATION SHEET/CHANGE OF ADDRESS

This Laboratory undertakes a continuing effort to improve the quality of the reports it publishes. Your comments/answers to the items/questions below will aid us in our efforts.

1. ARL Report Number ARL-TR-164 Date of Report July 1993

2. Date Report Received \_\_\_\_\_

3. Does this report satisfy a need? (Comment on purpose, related project, or other area of interest for which the report will be used.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

4. Specifically, how is the report being used? (Information source, design data, procedure, source of ideas, etc.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

5. Has the information in this report led to any quantitative savings as far as man-hours or dollars saved, operating costs avoided, or efficiencies achieved, etc? If so, please elaborate. \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

6. General Comments. What do you think should be changed to improve future reports? (Indicate changes to organization, technical content, format, etc.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

CURRENT  
ADDRESS

\_\_\_\_\_  
Organization

\_\_\_\_\_  
Name

\_\_\_\_\_  
Street or P.O. Box No.

\_\_\_\_\_  
City, State, Zip Code

7. If indicating a Change of Address or Address Correction, please provide the Current or Correct address above and the Old or Incorrect address below.

OLD  
ADDRESS

\_\_\_\_\_  
Organization

\_\_\_\_\_  
Name

\_\_\_\_\_  
Street or P.O. Box No.

\_\_\_\_\_  
City, State, Zip Code

(Remove this sheet, fold as indicated, tape closed, and mail.)  
(DO NOT STAPLE)

DEPARTMENT OF THE ARMY

OFFICIAL BUSINESS

**BUSINESS REPLY MAIL**

FIRST CLASS PERMIT No 0001, APG, MD

Postage will be paid by addressee

Director  
U.S. Army Research Laboratory  
ATTN: AMSRL-OP-CI-B (Tech Lib)  
Aberdeen Proving Ground, MD 21005-5066



NO POSTAGE  
NECESSARY  
IF MAILED  
IN THE  
UNITED STATES

